M-04 PARTS AND CUT SCHEDULE

TAPE MEASURE SATELLITE YAGI | TM-YAGI-01

DRAWING REV B

FOR REVIEW - SOURCE O3-O6 REV L

TAPE-STEEL FINISHED CUTS

10 PIECES | INCHES

APPROX. 3/8 in WIDE CONDUCTIVE TAPE STEEL

CUT ID	BAND	ELEMENT	FINISHED LENGTH	CUT TOL.	QTY
2M-R	2 m	Reflector	41.400	+/- 0.0625	1
2M-DE-L	2 m	Driven half - left	18.575	+/- 0.03125	1
2M-DE-R	2 m	Driven half - right	18.575	+/- 0.03125	1
2M-D1	2 m	Director 1	35.400	+/- 0.0625	1
70-R	70 cm	Reflector	12.900	+/- 0.03125	1
70-DE-L	70 cm	Driven half - left	6.175	+/- 0.0156	1
70-DE-R	70 cm	Driven half - right	6.175	+/- 0.0156	1
70-D1	70 cm	Director 1	11.900	+/- 0.03125	1
70-D2	70 cm	Director 2	11.900	+/- 0.03125	1
70-D3	70 cm	Director 3	11.700	+/- 0.03125	1

2 m NET LENGTH	**113.950**
70 cm NET LENGTH	**60.750**
INSTALLED NET STEEL	**174.700 in**

Each row is one finished cut; dimensions do not include the driven-element gap.

Driven half mismatch max: 2 m 0.03125 in; 70 cm 0.0156 in.

Driven tip gaps and installed tip-to-tip spans are controlled on M-06.

Measure after deburring and label every piece immediately.

Installed pieces shown; procurement stock and spare quantities follow O4.

NON-ELEMENT FINISHED PARTS

INSTALLED QTY

CUT ID	FINISHED SIZE	QTY
PVC-2M	30.000 +/- 0.0625 1/2 Schedule 40 PVC | 2 m boom	1
PVC-70	30.000 +/- 0.0625 1/2 Schedule 40 PVC | 70 cm boom	1
ST-1	12.000 +/- 0.0625 nom. 3/8 dowel / fiberglass | 2M-D1 support	1
ST-2	12.000 +/- 0.0625 nom. 3/8 dowel / fiberglass | 2M-DE support	1
ST-3	12.000 +/- 0.0625 nom. 3/8 dowel / fiberglass | 2M-R support	1
PAD-1	1.000 x 0.500 MIN; t >=0.375 nylon/acetal/HDPE | J1 separator	1
PAD-2	1.000 x 0.500 MIN; t >=0.375 nylon/acetal/HDPE | J2 separator	1

PVC pair finished-length difference <= 0.03125 in.

STEEL STOCK ALLOWANCE

MINIMUM USABLE

20 ft = 240.000 in

Installed finished tape pieces	**174.700 in**
Continuous reflector recut reserve	**41.400 in**
Coupon / cleanup / kerf / damage allowance	**23.900 in**

Installed + reserve = 216.100 in.

Keep one continuous 41.400 in section until cut inspection passes.

23.900 in covers losses; obtain more stock if exceeded.

PROPORTIONAL ALLOCATION ONLY; NOT A CUT ORDER.

GENERAL NOTES

1. ALL DIMENSIONS IN INCHES; QUANTITIES ARE INSTALLED FINISHED PARTS.
2. PAD PLAN DIMENSIONS MINIMUM; INSTALLED THICKNESS >= 0.375 in.
3. O7 HAIRPIN BLANK AND COAX CUTS ARE EXCLUDED FROM THIS O6 SCHEDULE.

SOURCE BASELINE
O3/O4/O5/O6 REV L
COMMIT 186c773

SCALE AT 100% PRINT
TABLES NTS
STOCK BAR PROPORTIONAL

ISSUE / DATE
REV B - FOR REVIEW
2026-10-12

SHEET M-04